RADCLIFFE

Contact Beds for Sewage Purification

Municipal Engineering
B. S.

1901

UNIVERSITY
OF
ILL. LIBRARY

Learning and Labor.
LIBRARY
OF THE
University of Illinois.
CLASS. BOOK. VOLUME.
1901 R11
Accession No.

204/208 Uofl

CONTACT BEDS

FOR

SEWAGE PURIFICATION

BY

WILLIAM HICKMAN RADCLIFFE

THESIS FOR DEGREE OF BACHELOR OF SCIENCE
IN MUNICIPAL AND SANITARY ENGINEERING

COLLEGE OF ENGINEERING
UNIVERSITY OF ILLINOIS
1901

1901
R11

CONTACT BEDS

FOR

SEWAGE PURIFICATION

BY

WILLIAM HICKMAN RADCLIFFE

THESIS FOR DEGREE OF BACHELOR OF SCIENCE
IN MUNICIPAL AND SANITARY ENGINEERING

COLLEGE OF ENGINEERING
UNIVERSITY OF ILLINOIS

1901

1901
R11

UNIVERSITY OF ILLINOIS

May 29, 1901 190

THIS IS TO CERTIFY THAT THE THESIS PREPARED UNDER MY SUPERVISION BY

William Hickman Radcliffe

ENTITLED Contact Beds for Sewage Purification

IS APPROVED BY ME AS FULFILLING THIS PART OF THE REQUIREMENTS FOR THE DEGREE

OF Bachelor of Science in Municipal and Sanitary Engineering.

A. N. Talbot

HEAD OF DEPARTMENT OF Municipal and Sanitary Engineering.

53820

Contact Beds for Sewage Purification.

It is the purpose of this thesis to present designs of sewage purification works applicable to the conditions of cities of the middle west where partial purification may have been effected by the septic tank process. It is assumed that the effluent, which is now discharged into small streams, will in the future require further purification.

To make the design fit real and varied conditions, the problem has been applied to two cities using septic tanks,— namely Champaign and Paris, Illinois. It may be of interest to note the general characteristics of the sewerage system of each place. Champaign has a long outfall sewer with

Digitized by the Internet Archive
in 2013

http://archive.org/details/contactbedsforse00radc

a flat gradient and with only five feet of fall from the top of the septic tank weir to the creek into which the effluent is discharged. Paris, on the other hand has a very desirable gradient in its outfall sewer, and at least eighteen feet of available fall from the weir of the septic tanks to the creek. In Cranbourne there is just enough fall to dispense with pumping, while in Paris the conditions are such that the beds can be economically built and efficiently operated.

The disposal works now in use in these cities are almost identical. Each comprises a well designed septic tank discharging into a small creek near by.

The effluent from the septic tanks and emptying the sewage to

purified by the contact beds, differs from the raw sewage in the following particulars

(a) The organic matters in suspension are almost entirely absent.

(b) Sand, cinders, and other particulate debris have been entirely removed.

(c) The organic matters in solution may have been increased.

(d) Compounds such as urea, albuminoid ammonia etc, have been more or less completely broken down and converted into marsh gas, carbonated ammonia, etc.

The effluent from the contact beds, which is the final effluent of the plant, differs from that of the septic tank in the following particulars.

(a) The ammonia is diminished.

(b) The total solids and organic matter

almost disappear.

(c) The nitrates and nitrites are greatly increased.

Only two methods are usually available for completing the purification of septic tank effluents. These are intermittent downward filtration and the contact bed. Contact beds are usually preferable to the filtration method for the following reasons:—

(a) The area required is smaller.

(b) The distribution over the bed does not have to be as thoroughly made and hence the distributing apparatus is much cheaper.

(c) Where natural sand beds are not available, the material for the beds is usually cheaper and can be obtained easily.

(d) The beds do not have to be cleaned periodically.

(e) The operation of the beds is simpler and does not require skilled labor.

(f) The deterioration is less and thus the cost of maintenance is reduced.

It may be affirmed, then, that for usual conditions in the middle west, contact beds are more economical than intermittent downward filtration areas. The effluent is comparatively pure. The action of contact beds on pathogenic bacilli - those of tubercle & typhoid has been investigated with the result that these infective materials have been completely destroyed. The effluent may be discharged into the bed of a stream without the least danger or nuisance.

Entering into the design of the contact bed are the following requirements:-

(a) The plant must be effective.

(b) It must be reasonably cheap.

(c) It must create no nuisance in the neighborhood of the disposal works.

(d) The process should if possible require no pumping of sewage.

(e) It should be automatic in action and should require little attention to insure successful operation.

The Design for Champaign.

The population of Champaign by the census of 1900 was 9,098. The city has the separate system of sewers and the sewerage conditions are now about the same as for a city of 6,000 or more inhabitants with all of the houses connected to the sanitary sewer. The outfall sewer extends for two miles through the city of Urbana, and because of the distance and the flat grade the sewage is over three hours in traveling from the main part of Champaign to the septic tank. Gaugings in the outfall sewer show a flow of 3,500,000 gallons per 24 hours during dry weather. The infiltration of ground water into the sewer often causes a flow of several times this amount.

The land available for disposal purposes, owned by the city, consists of a tract of 12 acres adjoining the east city limits of Arvada. The tract and general topography are shown on Plate 1.

The effluent from the septic tank is at present discharged into Ralt Creek, a small prairie stream. The usual dry weather flow in this stream is from 3 to 6 cubic feet per second, but during the excessively dry periods the flow stops entirely and during the spring freshets the discharge probably reaches 3000 c.f.s. per second. The area drained is about 55 square miles. The low land and the windings of the channel will necessitate the cutting of a new channel wide enough to carry the maximum flow, and the building of a dyke to keep the water

away from the disposal works. During the periods of night water, and when there is a large infiltration of ground water into the sewer, the effluent of the settling tanks may be discharged directly into the creek without offense.

The purification works herein presented comprise a grit chamber two septic tanks, a sludge removal plant, and twelve contact beds, with necessary distribution system. The works are designed for 20,000 people with an average sewage flow of 75 gallons per capita per 24 hours or 1,500,000 gallons per day. The actual capacity of the beds with voids at 25% is 1,503,400 gallons applying 2.7 doses per day.

The grit chamber (Plate 3) is divided into two compartments, each 4.2 x 12 ft.

and 4 ft. deep. When both chambers are working the sewage will be about two minutes in passing through. It is to be covered with a low brick building with sliding doors on either side so that, in cleaning, buckets of mud may be passed up and dumped into wagons directly. Distributing manholes in front and rear regulate the flow and make it possible to cut out one chamber for cleaning.

The present septic tank has a capacity of 22000 gallons. This is entirely inadequate for the sewage flow under consideration. A second septic tank will have to be built and is included in the design. The proposed septic tank has a cubic capacity of 44,000 gallons. This gives a total septic tank capacity of 66,000 gallons or 2.2 hours. The general design is like

that of the present septic tank (Plate 3). It is divided into two longitudinal compartments each 11 x 44 ft and 6 ft deep. The dividing wall has a 6 in. batter on each side and is 18 inches wide at the top. Each tank has a 12 in. opening into the sludge chamber which is located between the inlets. The openings are covered by sluice gates. The baffle board next to the discharging weir consists of three 2 in. oak boards arranged as shown in the accompanying sketch. The building covering the tank will be of the same height as the present one and of the same general design.



A slight change is planned for the present septic tank. A small sludge

chamber is to be constructed between the inlets and the pumping machinery in the building will be removed.

The bypass to the creek is of 18 in. line similar to the one now in use. The distributing manholes have simple hinged valves operated with a chain. The manhole at the junction of the discharging channel and the by pass has a sluice gate or partition dividing it into two parts. Thus the bypass and half the contact beds may be in operation at the same time.



There are 12 contact beds each 73 X 13 ft. with a depth of 3 ft. of contact material. For the average flow each bed is to receive 2.7 doses of sewage 24 hours. which gives

ample time for resting and aerating.

Six beds (numbered 1 to 6) are to be installed immediately. Considering the available voids as 25 o/o of the volume, each has a cubic capacity of 46,000 gallons. They are designed to treat an average flow of 751,700 gallons of sewage per 24 hours.

The beds are arranged in two rows and are separated by a 6-ft. clay wall. The 18 in. distributing main passes down between these rows of beds and the distribution is controlled by the Adams system which will be described later.

The contact material, considered to be available for the purposes of this design, is crushed flint from La Fayette, Ind. It is to be of such size that the particles will pass through a 1 in. ring and be caught on a number 4 sieve. It can be

purchased for $.80 per cu. yd. on board cars at Lafayette, which will make the cost about $1.50 per cu. yd. in place in the beds. Owing to inability to obtain samples of the material, a determination of the voids could not be made. Reasoning from other material of like character the voids were assumed to be 33⅓ %, and it was further assumed that the voids would be reduced to 25% after the beds have been in use for some time. 25% voids, then, was used in designing the system.

In order to secure additional fall it is planned to raise the weir of the old septic tank 0.6 ft. The effluent of the tanks will pass over the weir and into an 18-in. channel. It is then carried by two 18-in. distributing mains to the beds. 0.7 ft. is lost in the distribution.

The controlling device also causes a loss of 0.3 ft.

The sewage is then distributed through 12-in. tile, which discharges into a system of 8-in. half tiles whose gradient is such that the tile at the end sinks somewhat below the general surface of the bed. There are 13 outlets with 600 sq. ft. of surface for each to cover. On the surface of the bed, where the laterals discharge, are cut radiating channels and filled to insure a quicker and more even distribution.

Plate 4 shows this distribution.

The sewage passes through a depth of 6 feet of contact material. The effluent is collected by a series of 6 in. half tile laid on brick and placed 19 ft. apart. These discharge into two lines

of 12 in. tile which in turn discharge into a chamber from which the outlet syphon is served

The beds are discharged by a syphon with the loss of about 0.6 ft. Thus the total fall from the top of the weir of the septic tank to the bottom of the discharge pipe is 5 8 ft.

The walls between the beds are to be built of clay obtained in the excavation of the beds (Plate 6). They will be built up as the stone is thrown into the beds. The slopes are to be sodded to prevent wash by rain The slope on the channel side of the dyke will be covered with broken tile or brick stamped into the surface of the bank and a second layer laid on this Clay is to be used as a material for the

walls because of its ease of working and the low cost of construction. It is sufficiently near water tight to prevent serious leakage from one bed to another. A gravel drive passes among the beds and along the sides, for convenience in handling material and to afford inspection facilities for the plant.

Plate 7 gives sketches of the "Adams air-controlled sewage apparatus and Miller discharging siphon." The supply for the various beds is from an 18 in. distributing main common to all. Each bed is provided with a feed apparatus. This is in effect a simple D trap. The sewage enters freely until the bed is full when the liquid enters the chamber shown and rising around the larger dome forces the air from this

through an air pipe to the feed which creates an air lock and stops the further passage of the sewage until this air lock is freed by an added volume of air displaced from a smaller dome (as shown). The large dome stops the supply to its own bed; the small dome brings on the supply to the adjoining. Valves on the by passes are used to cut out a bed whenever necessary. The regulation is automatic and functions from bed to bed regardless of the volume dealt with.

In a chamber at the end of each bed is placed a special syphon. The latter is supplied with liquid from the bed through the stop-tap shown. An suction pipe attached to the summit of the syphon reaches over the chamber wall and dips into the liquid of the

beds. This chamber is surrounded by a brick wall laid open and has two lines of collecting tile running into it. The wall serves to keep the effluent from the suction pipe. The time taken to fill the dosing chamber and start the siphon is the measure of the time of contact; the regulating tap controls the flow of the effluent to the siphon chamber. The siphons are entirely free of the controlling apparatus and the time of contact is constant regardless of the flow.

In cleaning the septic tanks the sludge is carried from the sludge chambers through 12-in. pipes running into a sludge well 9 ft. in diameter and 15 ft. deep. From it is pumped by means of a 4-in. centrifugal pump

into the sludge pit This pit is an excavation of regular form just east of the contact beds It is tiled so that the water in the sludge will drain into the creek and the earthy matter remain behind and dry up. The engine, pump, and boiler are those now in use at the septic tank only half the sludge will be in the building, the remainder being covered with a removable platform so that it may be cleaned and the sludge hauled away in case the pump fails to act. The pump house is 20' x 16 ft. and is to be built of brick A little ornamentation of this building will add greatly to the general appearance of the plant and will not materially affect the cost of construction.

Estimate of Cost.

11,000	cu. yds. crushed flint @ $1.50	$16,500.00
18,000	cu. yds. excavation @ $.15	2,700.00
4,380	cu yds clay puddle @ $.08	350.
660	sq. yds riprap @ $.25	165.
4,000	cu. yds. gravel for drive @ $.75	3,000.
	Pipe	
Sewer	740 ft. - 18 in. @ $.24	$ 89.60
	7 - 18 in. crosses @ $1.40	9.80
	4 - 18 in. elbows @ $.85	3.40
	70 ft. - 12 in. @ $.15	10.50
	710 ft. - 8 in. @ $.08	56.80
	3 - 8 in. T's @ $.32	.96
	240 ft. - 4 in. @ $.04	9.60
Tile.	3,600 ft. - 12 in. @ $.09	324.00
	2,400 ft. - 8 in. @ $.042	100.80
	3,600 ft. - 6 in. @ $.027	97.20 1680.
Lagging	43,810 ft. B.M. @ $.02	875

carried forward ... $25,270.00

amount brought forward,	$ 25,270.00
New Septic Tank,	1,500.
Grit chamber,	500.
Pump house and sludge well,	1,200.
Adams controlling devices,	300.
5 manholes @ $ 15.00,	75.
Administration, supervision, etc.,	2,500.
Total cost,	$ 31,845.00

The system just described makes ample provision for a population of 20,000 people. To provide for a population of 12,000, the writer believes that the cost could be kept below $ 20,000. This would include the building of the first six beds, the new septic tank which must surely be installed in a short time, and the new screen for the race.

The efficiency of the system would undoubtedly be excellent. As sewerage continues to grow in the next twenty years

in the same ratio as in the past, the
will have a population of 30,000 people.
Long before this mark is reached, some
secondary purification will be of course
necessity. With this rapid growth in
view, it would be wise to make ample
provision for the future.

The Design for Paris

The population of Paris in 1900 was 6,105. The outfall sewer is 10 in. in diameter and has a minimum grade of .0025. The land available for sewage disposal purposes is a tract of 7.62 acres lying just north-east of the city limits. The tract and general topography are shown in Plate 8. The effluent from the septic tank is at present discharged into a small run which drains but five square miles and has very little flow. Because the flow of this stream is so small it is believed that a more complete purification will be necessary in the near future, and it is recommended that double contact beds be installed.

The purification system herein described is designed to have an average capacity of 1,000,000 gallons of sewage per 24 hours. It will consist of a grit chamber, an additional septic tank, a distributing reservoir, and primary and secondary contact beds

The grit chamber comprises two compartments, each 5 x 16 ft and 4 ft deep. When both chambers are working the capacity is 1 minute flow, if 1,000,000 gallons are flowing per 24 hours. The general design is the same as that for the champaign system

The present septic tank has a capacity of 30,000 gallons which is inadequate for the 1,000,000 gallons for which the beds are designed. A second septic tank having a cubic capacity of 45,000 gallons

is to be added. This gives a total septic tank cubic capacity of 75,000 gallons equal to 2 hours flow of sewage at the rate under consideration. The new tank is to consist of two compartments each 11 x 44 ft. and 7 ft. deep. (Plate C)

The distributing reservoir is circular in form and is 40 ft in diameter. It has an effective depth of 4 ft. The walls are 5.5 ft in height and are 25 ft. thick at the base and 13 in. at the top. The material is to be brick, lined with cement mortar. Earth is banked against the outside of the wall and has a slope of 1½ to 1.

Ten beds of the primary contact and five of the secondary are provided. The primary contact beds are 50 x 100 ft. and 4 ft. deep and are designed to receive

2.7 doses of sewage daily. Four are to be installed immediately which will permit the flow of 405,000 gallons of sewage per 24 hours the cubic capacity of each bed being 37,500 gallons.

The secondary contact beds are 45 X 140 ft. and are 4 ft deep. With 25% voids, each has a cubic capacity of 47,250 gallons. One will serve as second contact for two primary beds the number of doses of sewage being increased from 2.7 to 4.2 per day. Two secondary beds are to be installed at the beginning and one of the remainder whenever two of the first contact are built.

The contact material to be used in the construction of the beds is gravel with the building sand and dirt screened out. It can be obtained, cheaply, for

about $.80 per cu yd. For the purpose of this design the effective voids were assumed to be 25%.

The effluent from the septic tanks is discharged into an 18 in. concrete channel. It then is collected in the reservoir which has an effective depth of 4 ft. and a capacity of 37,500 gallons, the same as that of one of the beds of the first contact. The reservoir is discharged by a series of siphons, one for each bed of the primary contact. The discharging arrangement is as follows. A float is connected to a shaft by a rachet. Each time the liquid rises to the top of the reservoir, the shaft is rotated and brings a lug on the shaft in contact with a trip arrangement which in turn starts the discharge of the

syphon beneath it This allows the primary beds to be filled successively. .5 ft. head is lost in this operation.

The sewage is distributed over the beds by 8 in. tile (Bed 1 Plate 1) There are 13 openings and each serves 310 sq. ft. of surface. Radiating trenches from each opening serve to facilitate this distribution. The liquid passes through 4 feet of gravel and is collected by 10 lines of 4 in. hard vitrified tile. (Sec 3 + Fig 1.) This collection is slow and it may be throttled so that the liquid may remain in the tile for several hours. The throttling is accomplished by placing in the outlet pipe, a disc ~~and which~~ is an aperture to which is fixed six...

A 6-in. pipe carries the liquid to the secondary contact beds. It is tile lined

from 22 openings from 3-in. tile. (Bed 11. Plate 9). 0.5 ft. is lost in this distribution. Each opening covers about 290 sq. ft. of surface. After passing through 4 ft. of gravel, the liquid is collected by 15 lines of 3 in. tile resting on brick. The collection is so slow and the quantity flowing is so limited, at most times or usually, that a clogging filtration will give an imperfect contact. The final effluent is discharged from an 18-in tile.

The total difference in level from the septic tank weir to the bottom of the final discharge tile is 1.5 ft, allowing 1 ft. fall from the bottom of the secondary contact bed to the bottom of the final discharge pipe. The pipe and tile

- in 3 ft. above the bottom of the creek (Plate II.)

The sludge is discharged from an 8 in. pipe into a pit which is constructed in the creek bed. This pit is located in the Triangular portion of the disposal grounds and is screened from the rest of the plant by a hedge so that nothing unsightly might be seen from the road.

A gravel road leads through the beds to afford inspection facilities for the public.

Estimate of cost.

12,100 cu. yds. screened gravel @ $.80 ____ $ 9,680.00

6,000 cu. yds. excavation @ $.15 ____ 900.

800 cu. yds. clay puddle @ $.08 ____ 64.

415 cu yds. gravel for drive, @ $.75 ____ 312

Pipe

Sewer 700 ft. - 18 in. @ $.24 ____ $ 168.00

1300 ft. - 6 in. @ $.06 ____ 78.00

1150 ft. - 6 in. @ $.06 ____ 69.00

250 ft. - 4 in. @ $.04 ____ 8.00

7 - 18 in elbows @ $ 2.25 ____ 15.75

22 - 6 in. curves @ $.20 ____ 4.40

6 - 6 in. T's @ $.24 ____ 1.44

5 - 4 in. T's @ $.16 ____ .80

Tile 1,000 ft. - 12 in. @ $.09 ____ 99.00

1,600 ft. - 8 in. @ $.042 ____ 6.72

1,000 ft. - 16 in @ $.027 ____ 27.00

5,700 ft - 4 in @ $.015 ____ 86.50

3000 ft - 3 in @ $.01 ____ 30.00 ____ 558.

Carried forward ... $ 11,514.00

amount brought forward,	11,514.00
Laying 15,700 ft. @ $.02	314.
New Septic tanks	1,500.
Grit Chamber	500.
10 syphons for distribution system @ $25.00	250.
Reservoir	800.
5 manholes @ $15.00	75.
Superintendance, etc.	1600.
Total cost	$16,553.00

This installation is much cheaper than that designed for Champaign, chiefly because of the difference in the cost of the intact material. By building beds 1, 2, 3, 4, 11, and 12 only, the cost of extension should be about $12,000. For the present flow of sewage this cost could be further reduced by providing only single contact and, reducing the area to two beds.

PLATE 1



DISPOSAL GROUNDS

of the

CHAMPAIGN SEWERAGE SYSTEM

Area Acres

Scale 0 25 50 75 100 200

PLATE 2



PLAN OF SEPTIC TANKS AND CONTACT BEDS
CHAMPAIGN ILLS. Discharge Pipes ----
SCALE-1 inch = 60 feet Supply Pipes ——



Plan of Septic Tanks and Pump House
Champaign
Scale 1 in. = 15 ft.



Plan of

Contact Beds Nos. 2 and 4

Champaign

Showing Distribution and Collection

Scale 1in. = 20ft.

PLATE 5.



Longitudinal Section

Showing Elevations

Champaign

Scale 1 in. = 2 ft.



Wall Between Beds
Scale 1in = 2ft.



Wall Between Rows of Beds
Scale 1in = 2ft

Sections
of
Walls of Contact Beds
Champaign



Wall Between
Contact Beds
and Creek
Scale 1in = 4ft.

PLATE 7.

Sketch of
Adams Patent Controlling Devices
for
Champaign Contact Beds

Air-Controlled
Feed
Apparatus





Timed Discharging Syphon

PLATE 8



DISPOSAL GROUNDS

of the

PARIS SEWERAGE SYSTEM

Area - 7.62 Acres

Scale

PLATE 9


Fence Line
Gravel Drive
28'
Plan of
Septic Tanks
and
Contact Beds
PARIS ILLS.
Supply Pipes
Discharge Pipes
Scale 1 in. = 50 ft.
50'
1'
50'
1'
50'
1'
50'
30'
10
9
8
7
100'
15
140'
14
13
134' to fence
6" Discharge Pipes
6
5
4
3
2
100'
12" Tile spaced 14 ft. o.c.
6" Tile
Drive
15 Lines 3" ± Tile spaced 10 ft. o.c.
4"
12" Tile
18" Discharge Pipe
20'
20'
Gravel
Distributing Manholes
Present Septic Tank
Proposed Septic Tank
Reservoir dia. 40 ft.
18" By-pass
10'
26'
10" Pipe to Sludge Pit
Fence Line
1
12" Tile
8'
Hedge
Note Beds 1 to 10 are 50 ft. by 100 ft.
Beds 11 to 15 are 45 ft. by 140 ft.

PLATE 10.



Plan of
Septic Tanks
Paris

SCALE 1 in. = 15 ft.

Proposed Septic Tank

PLATE 11.



Longitudinal Section

Showing Elevations

Paris Contact Beds

Scale 1 in. = 4 ft.

UNIVERSITY OF ILLINOIS-URBANA
3 0112 086823553